GOVERNMENT OF MYSORE, STORES PURCHASE COMMITTEE, BANGALORE.

Notice No. 15111, *dated* 21*st June* 1929.

Sealed tenders for the supply of Mineral and Lubricating Oils required for the Mysore Railways, during the year 1929-30 will be received by the undersigned up to 12 noon on the 22nd July 1929.

2. A sum of Rs. 300 in cash towards earnest money should be remitted to the Officer in charge of the State Huzur Treasury, Bangalore, with chellans duly filled in by the tenderers, the fact of such remittance being noted in the tenders sent to this office. Cheques will not be received by the State Huzur Treasury Officer on this account.

3. Forms of tender and chellans for remitting earnest moneys may be obtained from the office of the Secretary, Stores Purchase Committee on payment of Rupees three only (in cash) being the price fixed for the form.

The forms will not be sent by V. P. P.

By Order,
E. V. GANAPATI IYER,
Secretary, Stores Purchase Committee.

IN THE COURT OF THE MUNSIFF OF NANJANGUD.

Insolvency Case No. 14 *of* 1928-29.

Subbanna, son of Linganna, Thammadi caste, residing at Thagadure, Belugairai Hobli, Nanjangud Taluk ... ... *Petitioner.*

vs.

(1) R. H. Setnu, R. N. Boys Company residing at Nanjangud ... *Opponents.*

Whereas the petitioner has applied to this Court, by a petition, dated 19th day of February 1929, to be declared an insolvent under the Mysore Insolvency Regulation VI of 1911, and your names appear in the list of creditors filed by the aforesaid debtor, this is to give you notice that the Court has fixed the 31st day of July 1929, for the hearing of the aforesaid petition and the examination of the debtor. If you desire to be represented in the matter you should attend in person or by duly instructed pleader.

Given under my hand and the seal of the Court this 28th day of June 1929.

U. D. NARAYAN MURTI,
Munsiff.

KOLAR DIVISION.

Dated 5th July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 27th July 1929, for restoring Krishnapur Kannegowdankere, Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Krishnapur Kannegowdankere, Malur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate of the probable cost of Restoring Krishnapur Kannegowdankere Reg. No. 280 and Serial No. 176 of Malur Taluk.

No.	Items	Per	Rate	Quantity	Cost	Total
	Bund R. L. 56·00		Rs.			
1	Earthwork to bund including all lead and lift with watering and tamping, etc., complete.	C.yd.		35·14		
2	Surki mortar concrete for core wall ...	C.ft.		313		
3	Burnt brick in surki mortar do ...	,,		1,861		
4	Puddle wall	C.yds.		297		
5	Turfing to bund	S.yd.		3,783		
6	Rough stone pitching new ...	C.yds.		94		
7	Resetting old stone revetment ...	L.S.		...		
8	New stone revetment	C.yds.		642		
9	Grade stones	No.		17		
10	Index stones	,,		17		
11	Register No. stones	,,		1		
12	Gauge stones	,,		1		
13	B. M. Stones	,,		2		
14	Removing jungle grades	Grades		13		
15	Cutting grips and removing ant hills, etc.	,,		13		
16	Repairs to lifting dam across weir halla with necessary requirements.	L. S.		..		
	Total for bund ...	...	...	...	...	
	Sluice at R. L. 43·00.					
1	Earthwork excavation	C.yds.		51		
2	Refilling the earth with consolidation ...	C.yds.		51		
3	Surki mortar concrete	C.ft.		379		
4	Burnt brick in surki mortar ...	,,		364		
5	Burnt stone slabs 4″ to 6″ thick ...	S.ft.		263		
6	Plastring with surki mortar ...	Sqr. yds.		7·01		
7	Providing plug and rod with locking arrangements, etc., complete.	L. S.		...		
8	Drilling holes in slabs	L. S.		..		
	Total sluice ...	...	...	...	...	
	Weir at R. L. 51·00.					
1	Earthwork excavation and using the earth to bund with consolidation	C.yds.		31·38		
2	Surki mortar concrete	C.ft.		549		
3	Burnt brick in surki mortar ...	,,		785		
4	Plastering with surki mortar ..	Sqr.		12·35		
5	Burnt stone slabs 4″ to 6″ thick ...	S.ft.		730		
6	New stone apron and revetment ...	C.yds.		216		
7	Providing joggle joints	No.		30		
	Total ...	...	...	...	...	
	Contingencies ...	...				
	Clearing jungle in the atchkat ...	Acars.		50		
	Grand Total ...	..	...	...	...	

Notice dated 5th July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 27th July 1929, for restoring Kondliganahalli Kallukunte Tank, Chintamani Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred and seventy-five in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Kondliganahalli Kallukunte Tank, Chintamani Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate of the probable cost of restoring Kondliganahalli Kallukote Regd. No. 266 of Chintamani Taluk, Kolar District.

o.	Items of work	Per	Rate	Quantity	Cost	Total
	Bund.		Rs. a. p.			
	Earthwork including water and tamping, etc., complete including lead and lift.	C.yds.		5,376		
	Turfing	S.yds.		4,488		
	Resetting old stone with new jelly	C.yds.		278		
	New stone work	,,		965		
	Fixng new grade stones as detail	No.		15		
	Do index stones	,,		15		
	Do B. M. Stones	,,		2		
	Do Red. No. and date stone ...	,,		1		
	Do Gauge stone	,,		1		
	Cutting hongey trees and rooting them out wherever existing,	Lump	sum	rupees		
	Breach filling.					
	Removing loose soil...	Lump	sum	rupees		
	Earthwork to breach including consolidation ...	C.yds.		957		
	Stone Pitching	,,		64		
	Gravel backing	,,		58		
	Puddlewall	,,		173		
	Earthwork excavation	,,		55		
	Total Bund ...	...	...	...		

No.	Items of work	Per	Rate	Quantity	Cost	Total
	Sluice No. 5.		Rs. a. p.			
1	Earthwork excavation	C.yds.		87		
2	Do refilling with watering and tamping, etc., complete.	,,		72		
3	Surki concrete	C.ft.		287		
4	Burnt brick in surki	,,		328		
5	Burnt stone slabs	S.ft.		223		
6	Surki mortar plastering	Sqr.		6·04		
7	Drilling holes	Lump	sum	rupees		
8	Providing plug and rod with locking arrangements	,,	,,	,,		
	Total sluice No. 1 ..	..	...	...		
	Sluice No 2.	As per	Sluice	No. 1.		
	Waste weir.—					
1	Earthwork excavation	C.yds.		246		
2	Surki concrete	C.ft.		139		
3	Burnt brick in surki	,,		681		
4	Burnt stone slab	S.ft		381		
5	Surki mortar plastering	Sqr.		9·72		
6	New stone work	C.yds.		103		
7	Resetting old stone with new jelly... ...	,,		27		
8	Providing joggle joints	No		15		
	Total waste weir ...	...	...	...		
	Total bund, sluice and waste weir ...	...	...	...		
	Contingencies at 5 per cent ...	...	...	..		
	Grand Total Rupees ...	...	...	...		

Notice, dated 5th July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division up to 2 P.M. of 27th July 1929, for improving the Munsiff's Court at Chikballapur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the Munsiff's Court at Chikballapur " in default of which, tenders will be rejected

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderer stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Detail Abstract Estimate for improving the Munsiff's Court at Chikballapur, Kolar District.

No.	Items of work	Per	Total Quantity	Rate	Cost	Total
1	Dismantling parapet wall	C.ft.	105			
2	Dismantling coping over the compound wall for raising the wall.	,,	58½			
3	Earthwork excavation for foundation ...	C.yds.	25			
4	Jelly concrete in chunam	C.ft.	176			
5	Burnt stone in mud for foundation	,,	367			
6	Burnt brick in mud	,,	1,144			
7	Burnt brick in chunam as per deduction above ...	,,	193			
8	Burnt stone slabs dressed 6" thick	S.ft.	298			
9	Cut stone beam dressed	C.ft.	14¾			
10	Burnt stone pillars dressed 6" thick	S.ft.	42			
11	Teakwood panelled door in place of window for main building.	,,	133			
12	Teakwood windows with panelled shutters with iron bars including glass ventilators attached at top complete.	,,	60			
13	Expanded metal from 1" mesh for door way ...	,,	64			
14	Steel joists	Cwt.	23¼			
15	Teakwood work wrought and put up including wood oiling.	C.ft.	22·08			
16	Terrace roofing with jackarch	Sqr.	5·87			
17	Mangalore roof tiles on teak reepers... ...	,,	3·75			
18	Ornamental eave board	R.ft.	31			
19	Plastering with chunam	Sqr.	21·00			
20	Cornice work 9" thick above	R.ft.	132			
21	Parapet wall 2' high alround	,,	132			
22	Chunam borders	,,	68			
23	Burnt stone flooring on concrete bed ...	Sqr.	6·86			
24	White washing as per plastering	,,	21·00			
25	Chocolate painting	,,	6·00			
	Total ...	...	...			
	Unforeseen items ..	...	L. S. Rs.			
	Total ...	...	...			
	Contingencies at 5 per cent ...	...	...			
	Grand Total ..	...	...			

N. LAKSHMINARASIMIAH,
Executive Engineer

BANGALORE DIVISION.

Dated 9th July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 23th July 1929, for completing the new tank across Maralwady stream near Mavathur Village Kankanhalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M., on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. A. Tenders quoting percentages below or above will not be accepted.